BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE

Office of the Executive Engineer Dasarahalli Division,

SCHEDULE-B

Name of Work: Improvements of Roads and Drains in Sampangi Ramaiah Layout of Sidedahalli Village, Ward.No. 14, Bangalore

Sl. No	Description of work	Unit	Qty	Rates to be Quoted	
				In Figures	In Words (Rs.)
	2	3	4	5	6
	Excavation for road, drains and similar works - KSRRB 300-2. Earthwork excavation by manual means in hard soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed the disposed earth to be leveled neatly after breaking of clods complete as per specifications.	Cum	312.00	81.00	Rupees Eighty One Only
	Providing and laying in position plain cement concrete of mix M7.5 with OPC cement @180 kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @0.57cum machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation etc. complete including cost of all materials, labour, HOM of [illegible] complete as per specifications.	Cum	46.80	3812.82	Rupees Three Thousand Eight Hundred Twelve and Eighty Two Paise Only
	Providing and laying in position plain cement concrete of design mix M20 with OPC cement @320 kgs, with 20mm and down size graded granite metal coarse aggregates @0.878cum and fine aggregates @0.50cum with superplastisiser @3lts. confirming to IS:9103-1999 Reaffirmed-2008, machine mixed, concrete laid in layers cut blocks, anchor blocks, plain window sills filled in [illegible] cost of all materials, labour, HOM of [illegible] curing, complete as per specifications.	Cum	117.00	5142.06	Rupees Five Thousand One Hundred Forty Two and Six Paise Only
	Providing TMT steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping, and / or welding wherever required, tying with [illegible] wire and anchoring to the adjoining members [illegible] complete as per design (laps, hooks and [illegible] shall not be measured and paid) cost of materials, [illegible], HOM of [illegible] complete as per specifications.	q	77.38	7187.86	Rupees Seven Thousand One Hundred Eighty Seven and Eighty Six Paise Only
	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls of any thickness, including attached pilasters, buttresses, plinth and string courses cost of all materials [illegible] complete as per specifications.	Sqm	780.00	239.56	Rupees Two Hundred Thirty Nine and Fifty Six Paise Only

Technical Manager(TM-2)
KRIDL, Dasarahalli Zone, Bangalore

EXECUTIVE ENGINEER
Bruhat Bangalore Mahanagara Palike
Dasarahalli Division, Bangalore-73

6	Supplying and fixing precast rainforced concee slab 10cm thick including cost of reinforcement as per design and drawing material cost, transportation, hire charges of machinery, machine cutting the vertical face to get plain even surface etc., complete with all leads and lift conveyance charges, labour charges inclusive of cost of all materials, complete as per specifications.	Sqm	260.00	1600.00	Rupees One Thousand Six Hundred Only
7	Lead for Disposal of Debris shall be payable at carage rates be mechanical means - With all lead, lifts, loading and unloading charges, cost and conveyance of all matrials, labour, equipments - 10Kmtrs etc. complete as per specifications.	Cum	312.00	78.24	Rupees Seventy Eight and Twenty Three Paise Only

Signature of the Contractor

(TM-2)
KRIDL, Dasarahalli Zone, Bangalore

Executive Engineer,
Dasarahalli Division,